

Case study

DHL Hams Hall distribution facility



Key facts

Key vendors: DHL
Site: DHL
Sector: Industrial
Client: DHL
Contractor: McDermott Construction

Brief

DHL had for some time experienced problems with cracking to the external paving at their Hams Hall distribution facility. Round the clock access by 42 tonne articulated vehicles dictated a construction regime that gave access to completed concrete slabs at 24 hours.

Solution

Diamondcrete RA, a fast curing high strength concrete was proposed to McDermott Construction to meet both operational deadlines for return to use.

The high ultimate strength achieved by Diamondcrete RA, typically in excess of 85N/mm² affords significant whole life costs benefits over traditional concrete grades.



Tel:01530 510066

www.aggregate.com

A member of the Holcim Group